



LATEST REVISION DETAILS		NAME	DATE
ISSUED FOR TENDER		BF	20-04-11
NOTES 1. ALL SEDIMENT AND EROSION CONTROL MEASURES ARE TO BE CONSTRUCTED IN ACCORDANCE WITH THE AUCKLAND REGIONAL COUNCIL'S TECHNICAL PUBLICATION NO. 90 MARCH 1999. 2. BEFORE COMMENCING WORKS THE CONTRACTOR SHALL ENSURE THAT THEY HAVE A COPY OF THE RESOURCE CONSENT FROM THE ENGINEER. 3. ANY MODIFICATIONS TO THE CONSENTED SILT CONTROL DRAWING MUST BE APPROVED BY THE ENGINEER PRIOR TO CONSTRUCTION. 4. THE EXTENT OF AREAS TO BE WORKED ARE TO BE CLEARLY IDENTIFIED PRIOR TO STRIPPING AND ALL SILT CONTROL MEASURES IN PLACE AND APPROVED BEFORE EARTHWORKS COMMENCE. 5. SITE ACCESS IS SUBJECT TO WAITAKERE CITY COUNCIL APPROVAL. 6. EXTENT OF EARTHWORKS AREA = 925m². 7. CONTOURS SHOWN IN THIS DRAWING REFER TO DESIGN FINISH LEVEL.			
LEGEND EXTENT OF WORKS EXISTING CONTOURS FINAL CONTOURS CLEAN WATER DIVERSION SILT FENCE STORMWATER LINE CESSPIT			
CLIENT:  Waitemata District Health Board <i>Te Wai Awhina</i>			
 WOODS Engineers. Surveyors. Planners. <small>PO BOX 6752, WELLESLEY ST, AUCKLAND 1141 BLDG 3, LEVEL 4, 666 GREAT SOUTH ROAD, PENROSE PHONE +64 9 571 2470 FAX +64 9 571 3405 WWW.WOODS.CO.NZ</small>			
FIXED ORAL HEALTH CARE UNITS			
HENDERSON INTERMEDIATE SCHOOL 6-CHAIR FACILITY EARTHWORKS PLAN (SHEET 2 OF 2) WAITAKERE CITY COUNCIL			
DESIGNED: SK	FOR TENDER		
CHECKED:	DRAWN: SK		
APPROVED:	SURVEYED: SG & RC		
JOB NUMBER: 60541	SCALE: 1:200 @ A3		
ISSUED: 20-04-10			
DWG. NO. 60541-03-EW-101	REV. -		