



LATEST REVISION DETAILS	NAME	DATE
SERVICE TRENCH & DRIVEWAY SETOUT DIMENSIONS ADDED	BF	13-09-16

NOTES

1. ALL WORK AND MATERIALS TO COMPLY WITH WCC ENGINEERING STANDARDS. ANY AMBIGUITY BETWEEN DRAWINGS AND COUNCIL STANDARDS TO BE REPORTED TO THE ENGINEER FOR CLARIFICATION.
2. KERB TO BE SLIPFORMED VERTICAL KERB & CHANNEL OR SLIPFORM KERB & NIB AS SHOWN.
3. ALL SINGLE CESSPIITS TO BE 675mm X 450mm.
4. FOOTPATHS TO BE CONSTRUCTED AS PER DETAILS ON TYPICAL CROSS SECTION DRAWINGS.
5. PRAM CROSSINGS TO BE CONSTRUCTED AS PER WCC DETAIL.
6. VEHICLE CROSSINGS TO BE CONSTRUCTED AS PER WCC DETAIL WITH ONE LAYER OF 665 MESH CENTRALLY PLACED IN ALL CASES.
7. PAVING IS TO BE CONSTRUCTED AS PER THE DETAILS INCLUDED IN THIS DRAWING SET.
8. ALL LANE MARKING AND ROAD SIGNAGE IS TO BE CONSTRUCTED AS PER TRANSIT NEW ZEALAND MANUAL OF SIGNS AND MARKINGS.
9. FOOTPATH TO BE EXPOSED AGGREGATE FINISHED.
10. BEND RADIUS IS MEASURED TO THE FACE OF KERB.
11. SPOT LEVELS SHOWN IN THIS DRAWING REFER TO LEVELS AT TOP OF KERB OR LIP OF CHANNEL AS SHOWN.

**NOTE**

	387763.79, 801354.67
--	----------------------

 DENOTES SETOUT POINTS. MARKED WITH ENGINEERING PEGS

CLIENT:	
---------	--



PO BOX 6752, WELLESLEY ST, AUCKLAND 1141  
BLDG 3, LEVEL 4, 666 GREAT SOUTH ROAD, PENROSE  
PHONE +64 9 571 2470 FAX +64 9 571 3405 [WWW.WOODS.CO.NZ](http://WWW.WOODS.CO.NZ)

## FIXED ORAL HEALTH CARE UNITS

HENDERSON INTERMEDIATE  
SCHOOL  
6-CHAIR FACILITY  
SET OUT PLAN

WAITAKERE CITY COUNCIL

DESIGNED: SK	ISSUED FOR CONSTRUCTION	
CHECKED:		DRAWN: SK
APPROVED:		SURVEYED: SG & RC
JOB NUMBER: 60541		SCALE: 1:200 @ A3
ISSUED: 23-07-10		

60541-03-GE-025

REV.	
------	--