



| LATEST REVISION DETAILS | NAME | DATE     |
|-------------------------|------|----------|
| ISSUED FOR TENDER       | BF   | 20-04-10 |

#### NOTES

1. ALL SEDIMENT AND EROSION CONTROL MEASURES ARE TO BE CONSTRUCTED IN ACCORDANCE WITH THE AUCKLAND REGIONAL COUNCIL'S TECHNICAL PUBLICATION NO. 90 MARCH 1999.
2. BEFORE COMMENCING WORKS THE CONTRACTOR SHALL ENSURE THAT THEY HAVE A COPY OF THE RESOURCE CONSENT FROM THE ENGINEER.
3. ANY MODIFICATIONS TO THE CONSENTED SILT CONTROL DRAWING MUST BE APPROVED BY THE ENGINEER AND ARC PRIOR TO CONSTRUCTION.
4. THE EXTENT OF AREAS TO BE WORKED ARE TO BE CLEARLY IDENTIFIED PRIOR TO STRIPPING AND ALL SILT CONTROL MEASURES IN PLACE AND APPROVED BEFORE EARTHWORKS COMMENCE.
5. SITE ACCESS IS SUBJECT TO ARC AND NORTH SHORE CITY COUNCIL APPROVAL.
6. EXTENT OF WORKS AREA =  $XXm^2$ .
7. TOTAL CUT VOLUME =  $XXm^3$   
TOTAL FILL VOLUME =  $XXm^3$   
BALANCE =  $XXm^3$  EXCESS CUT

#### LEGEND

- EXTENT OF WORKS
- EXISTING CONTOURS
- FINAL CONTOURS
- CLEAN WATER DIVERSION
- EARTH BUND
- SILT FENCE
- STORMWATER LINE
- CROSSPT
- CLIENT:



**Waitemata**  
District Health Board  
*Te Wai Awihina*



**WOODS**  
Engineers, Surveyors, Planners.

PO BOX 4752, WELLSLEY ST, AUCKLAND 1141  
BLDG 3, LEVEL 4, 666 GREAT SOUTH ROAD, PENROSE  
PHONE +64 9 571 2470 FAX +64 9 571 3405 [WWW.WOODS.CO.NZ](http://WWW.WOODS.CO.NZ)

## FIXED ORAL HEALTH CARE UNITS

GLENFIELD INTERMEDIATE SCHOOL  
4-CHAIR FACILITY  
EARTHWORKS PLAN  
NORTH SHORE CITY COUNCIL

|                          |                   |        |
|--------------------------|-------------------|--------|
| DESIGNED: SK             | DRAWN: SK         | TENDER |
| CHECKED:                 | SURVEYED: SC & RC |        |
| APPROVED:                | SCALE: 1:300 @ A3 |        |
| JOB NUMBER: 60541        |                   |        |
| ISSUED: 20-04-10         |                   |        |
| DWG. NO. 60541-02-EW-100 |                   | REV. - |